1825 K Street NW, Suite 1100 Washington, D.C. 20006 INTERIOR IMPROVEMENTS

4TH FL JUVENILE INTAKE & MENTAL HEALTH DIV H CARL MOULTRIE COURTHOUSE 500 INDIANA AVE, WASHINGTON, D.C. 20001 DISTRICT OF COLUMBIA COURTS

CAPITAL PROJECTS & FACILITIES MANAGEMENT DIVISION

SUB TOTAL

	Description	Quantity	Unit	Rate	Total
1.0	SPECIAL CONDITIONS				
	Mental Health Division - see drg A0005				
	Phasing & Protection				
	Step 1				
	Remove double-seat furniture to Court's		LS		
	warehouse				
	Remove door w/frame & hardware, single	1.00	EA		
	Remove gypboard partitions & finishes to form cased opening	40.00	SF		
	Cased opening, hollow metal frame, interior, single	1.00	EA		
	Wall type 1 - 3 5/8" metal stud, 1 layer fire- rated gypboard type X each side, 3 1/2" sound attenuation blanket, door infill	32.00	SF		
	Base, rubber, 4" high	20.00	LF		
	Paint @ partitions	120.00	SF		
	Paint @ cased opening	54.00	SF		
	Patch & repair where door removed	1.00	LS		
	Patch & repair where cased opening formed	1.00	LS		
	212				
	Step 2	0.00			
	Install re-used task chair from Court's warehouse	3.00	EA		
	Re-install systems furniture (work station & storage) from Court's warehouse	3.00	EA		
	Adapt existing power, data, telephone to accommodate systems furniture (work station & storage) - allowance	1.00	LS		
	Step 3				
	Remove work stations to Court's warehouse	4.00	EA		
	Remove chairs to Court's warehouse	4.00	EA		

	Description	Quantity	Unit	Rate	Total
	Step 4	_			
	Wall type 1 - 3 5/8" metal stud, 1 layer fire- rated gypboard type X each side, 3 1/2" sound attenuation blanket, temporary demising	181.50	SF		
	Base, rubber, 4" high	26.00	LF		
	Paint @ partitions	300.00	SF		
	Step 5				
	Remove gypboard partitions & finishes	693.00	SF		
	Remove door w/frame & hardware, single	1.00	EA		
	Supervision & Coordination				
	Phasing supervision & coordination - allowance	1.00	LS		
	Subtotal				
2.0	DEMOLITION & SITE WORKS				
	Demolition				
	Remove floor covering w/sub-base	2,597.00	SF		
	Remove gypboard partitions & finishes	2,112.00	SF		
	Remove suspended ceiling	2,579.00	SF		
	Remove window coverings & hardware	280.00	SF		
	Remove door w/frame & hardware, single	5.00	EA		
	Remove art work & other wall-mounted furnishings as directed by Owner - allowance	1.00	LS		
		0.4.00			
	Protect millwork during works	21.00	LF		
	Protect floor finishes during works	1,068.00	SF		
	Protect ceiling finishes during works	1,068.00	SF		
	Disposal				
	Cart away & disposal	125.00	CY		
	Subtotal	123.00	Ci		
	CONODETE				
3.0	CONCRETE				
4.0	MASONRY				
5.0	METALS				
	Miscellaneous metalwork	3,181.00	SF		
	Subtotal				

	Description	Quantity	Unit	Rate	Total
6.0	WOOD AND PLASTIC		011110	1 1445	
	Cabinets, plastic laminate - below @ Service Counter	14.00	LF		
	Plastic laminate countertop w/splashback @ Service Counter	14.00	LF		
	Rough carpentry, blocking etc	3,181.00	SF		
	Subtotal				
7.0	THERMAL AND MOISTURE PROTECTION				
	Misc joints, sealants & fire blocking	3,181.00	SF		
	Subtotal				
8.0	OPENINGS	10.00			
	Door, wood, solid core w/hollow metal frame & hardware, interior, single	13.00	EA		
	Subtotal				
9.0	FINISHES				
	Floors				
	Patch & prepare sub-base w/1/8" self- levelling compound	2,597.00	SF		
	Carpet tile, 24" x 24" wide	2,566.00	SF		
	Resilient tile @ refrigerator area	31.00	SF		
	Transition strip @ refrigerator area	6.00	LF		
	Daga wikhar 4" high	051.00	1.5		
	Base, rubber, 4" high Saddle threshold @ cased opening	851.00 1.00	LF EA		
	Saddle tillesiloid @ cased openling	1.00	LA		
	Partitions				
	Wall type 1 - 3 5/8" metal stud, 1 layer fire- rated gypboard type X each side, 3 1/2" sound attenuation blanket	5,284.13	SF		
	Wall type 2 - 3 5/8" metal stud, 1 layer fire- rated gypboard type X one side, 3 1/2" sound attenuation blanket	121.28	SF		
	Walls				
	Patch & prepare existing for new finishes	4,220.00	SF		
	Patch, repair @ window surrounds	304.00	SF		
	Paint @ partitions	6,240.00	SF		
		•			
	Paint @ window surrounds Stain/paint door & frames, single	244.00 14.00	SF EA		
	Stanzpant door a names, single	11.00			

	Description	Quantity		Rate	Total
	Ceilings				
	ACT-1 - Acoustical ceiling tiles, 2' x 2' x 3/4", suspended, tegular	2,579.00	SF		
	Subtotal				
10.0	SPECIALITIES				
	Coat hooks @ office doors	9.00	EA		
	Cabinet w/extinguisher, recessed	1.00	EA		
11.0	Subtotal				
11.0	EQUIPMENT				
	Pantry Refrigerator, clean & re-install - (no water line)	1.00	EA		
	Subtotal				
12.0	FURNISHINGS				
	Mini-blinds, aluminum, horizontal, 1" wide	280.00	SF		
	Relocate systems furniture (work station) from existing suit & reconfigure - AK02	1.0	LS		
	Relocate safe from existing suite - AK03	1.00	EA		
	Install re-used lateral file from Court's warehouse - AK04	5.00	EA		
	Install re-used 48" dia round meeting table from Court's warehouse - AK05	1.00	EA		
	Relocate lateral files & storage cabinets from existing suite - AK06	20.00	EA		
	Install re-used service counter w/systems panels from Court's warehouse, 96" long consisting of 2 no. 48" work stations - AK08	1.00	EA		
	Relocate task chairs from existing suite, type G131-EX - AK09	16.00	EA		
	Install re-used task chair from Court's warehouse, type XG-131- AK11	9.00	EA		
	Relocate wood credenza from existing suite - AK10	1.00	EA		
	Install re-used coat racks from Court's warehouse - AK14	2.00	EA		
	Install re-used court typical workstations from Court's warehouse	4.00			
	Relocate mail sorter from existing suite - AK15	1.00	EA		
	Subtotal				

	Description	Quantity		Rate	Total
13.0	SPECIAL CONSTRUCTION	4444		1 10.55	1 0 10.1
10.0					
14.0	CONVEYING EQUIPMENT				
1 1.0	OSITVETING EQUI MENT				
15.1	PLUMBING				
10.1	T LOWER TO				
15.2	HVAC				
10.2	VAV Boxes	9.00	EA		
	Registers & Diffusers	31.00	EA		
		7.00	EA		
	Drip Trays w/ Sensors Sheet Metal	3,248.00	LBS		
	Insulation / Liner - Sheet Metal	1,688.96	SF		
		7.00	EA		
	Connect to Existing Sheet Metal	335.00	LF		
	Hot Water Piping	335.00	LF		
	Insulation - Piping	4.00	EA		
	Connect to Existing Piping Controls - VAV / Thermostats	9.00	EA		
		1.00	LS		
	Integrate Controls into Existing BMS	16.00	HRS		
	Testing Adjusting & Balancing Coordination	24.00			
		1.00	HRS LS		
	Cut Cap Drop Make Safe - Sheet Metal	1.00	LS		
	Cut Cap Drop Make Safe - Piping				
	Cut Cap Drop Make Safe - Controls	1.00	LS LS		
	Remove & Dispose	1.00	LS		
15.3	Subtotal				
15.3	FIRE PROTECTION	1.00	EA		
	Connect to Existing Risers	1.00	EA		
	Control Valve Assembly Wet Sprinkler Building Coverage		SF		
	vvet Sprinkler Building Coverage	2,841.00	SF		
	Cultatal				
10.1	Subtotal				
16.1	ELECTRICAL				
	Demo Works	71.00			
	Disconnect & Remove Ceiling Outlet & Lighting Outlet Fixture	71.00	EA		
	Disconnect & Remove Switch & Wiring Back Box	7.00	EA		
	Disconnect & Remove Blank Wall plate	13.00	EA		
	Disconnect & Remove Wiring Devices	16.00	EA		
	Disconnect & Remove Fire Alarm Devices	10.00	EA		
	Disconnect & Remove Power Pole	1.00	EA		
	Disconnect & Remove Camera	1.00	EA		
	Disconnect & Remove Data Outlet	8.00	EA		
	Disconnect & Remove Door Bell	2.00	EA		
	Disconnect & Remove Door Motion Sensor	1.00	EA		
	New Works				

Description		Quantity	Rate	Total	
Lighting					
R1- 2'X2'		41.00	EA		
R1B- 2'X2'		15.00	EA		
X - Exit Light		6.00	EA		
3/4" EMT		1,550.00	LF		
#12		4,650.00	LF		
Lighting Controls		1,000.00			
Single Pole Switch		3.00	EA		
Occupancy Sensor		11.00	EA		
Room Controller		2.00	EA		
Other Misc. Lightin	Control Devices	9.00	EA		
18/3 LV Wires + Ou		22.00	EA		
3/4" EMT	illet boxes	75.00	LF		
		225.00			
#12		225.00	LF		
White a Davidson					
Wiring Devices		FC 00	_ ^		
Duplex Receptacle		56.00	EA		
Duplex Receptacle		2.00	EA		
Double Duplex Red		8.00	EA		
Furniture Feed Cor		4.00	EA		
Power & Communi	cation Wall Box	2.00	EA		
Junction Box- FF		4.00	EA		
3/4" EMT		1,900.00	LF		
#12		5,700.00	LF		
Fire Alarm Devices		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			
Control Module		2.00	EA		
Visual Device		1.00	EA		
Audio/Visual Devic		5.00	EA		
3/4" EMT	<u> </u>	200.00	LF		
Teflon Cables		220.00	LF		
Testing and Tie into	a evicting evetem	1.00	LS		
	CABING SYSTEM	1.00			
Telecommunication	n Devices				
Tele/Data Outlet	I DEAICES	15.00	EA		
Data Outlet		2.00	EA		
Data Outlet		2.00	LA		
3" Sleeves		1.00	EA		
1" EMT stun ups		340.00	LF		
Cat 6 Cables - sup separate contract	oly & install under	3,740.00	LF		
Testing, tie into exi	sting system &	1.00	LS		
	r separate contract	1.00			
Misc. Conditions					
Card Reader w/ wir	ing and tie into system	1.00	EA		

	Description	Quantity	Rate	Total	
	20A Breakers w/ terminations	35.00	EA		
	Testing and Commissioning	1.00	LS		
	As Built, Shop Drwgs, etc.	1.00	LS		
	Subtotal				
16.2	AUDIO-VISUAL				
	Video Display Equipment				
	60" LCD flat panel screen - supply & install by AV Consultant	2.00	EA		
	Wall-mounting for 60" LCD flat panel screen - supply & install by AV Consultant	1.00	EA		
	Ceiling-mounting for 60" LCD flat panel screen - supply & install by AV Consultant	1.00	EA		
	Subtotal				
17	General Conditions				
17.1	Site Management				
	Labor				
	1				
	2				
17.2	Material Handling				
	1				
	2				
	3				
	4				
	SUB TOTAL				
	To Summary				
18	OVERHEAD (%)		%		
19	PROFIT (%)		%		
	SUB TOTAL				
20	BONDS				
21	INSURANCES, ETC				
<u> </u>	SUB TOTAL				
	TOTAL ESTIMATED				
	TOTAL ESTIMATED				